

# Summit



Shaker Mortise and Tenon Door, Veneer Flat Panel, Solid Drawer Front, Square Edge Profile, Maple Hardwood, Full Overlay

*Now Available In Stock*

## Features

### Durable, Plywood Construction

Cabinet boxes are made using all plywood construction with a light maple interior.

### Wide Range of Sizes

Variety of cabinet sizes in stock for multifamily kitchen and bath projects.

### Soft-Close Doors

Standard 6-way adjustable hinges with soft-close feature to prevent slamming.

### Soft-Close Drawers

Dovetail construction with steel undermount soft-close glides.

### Available for Quick Ship

Locally stocked in our Braintree, MA warehouse for fast and convenient delivery.

## Stock Color

*Other colors are available via special order. See your sales rep for details.*



ELEGANT WHITE


# All Plywood Construction



## At a Glance


- Plywood construction
- 5/8" Nominal (16 mm) solid dovetail drawers with 1/4" Plywood Bottoms
- 3/4" Nominal (18 mm) plywood shelves with light maple laminate and matching PVC edge banding
- Laminate interior and exterior sides

## Detailed Specifications




### Adjustable Hinges

Heavy duty, self closing, and concealed within the cabinet door and frame. Soft close option available.




### Drawer Sliders

75 lb load rated, epoxy coated slides. Upgrades to 100 lb full extensions and 75 lb undermount soft close full extension are available.




### Solid Dovetail Drawers

5/8" featuring four sided construction and captive 1/4" Nominal (6.4 mm) matching plywood bottom.




### Door and Drawer Fronts

Assembled with kiln-dried solid American hardwood.




### Edgebanded Plywood Shelves

3/4" Nominal (18 mm) provide both a matching appearance with the interior of the cabinet, and improved water resistance.




### Face Frame Stile and Rails

3/4" thick by 1 1/2" Nominal (18 mm by 38 mm) wide kiln-dried hardwood. Frames are assembled under pressure with pocket screws.




### Wall and Base Backs

1/2" Nominal (12 mm) plywood with light maple laminate interior. Wall backs are stapled and glued into rabbeted ends.




### Wall and Base Sides

1/2" Nominal (12 mm) plywood with light maple laminate interior and designated laminated exterior.




### Base Bottoms

1/2" Nominal (12 mm) plywood with light maple laminate interiors. Bottoms are hot melt glued into dados on all four sides.




### Wall Tops and Bottoms

1/2" Nominal (12 mm) plywood with light maple laminate, hot melt glued into dados on all four sides.



### I-Beam Construction Rails

1/2" Nominal (12 mm) plywood. Rails are hot melt glued into face frame, sides, and cabinet back.



### Standard Toe Kicks

Measure 3 1/2" deep by 4 1/2" tall. 9" universal access toe kick available on most cabinet models.